ARIZONA Public Service COMPANY
P. O. BOX 2591 • PHOENIX 2

ESTIMATE OF OPERATING COST

of

YEAR ROUND AIR CONDITIONING

for

VILLA MONTEREY UNIT #2

Stated below is Arizona Public Service Company's estimate of the operating costs of an electric air-to-air heat pump for year-round air conditioning of VILLA MONTEREY UNIT #2. It must be pointed out that these figures do not include electric energy consumed for lights, cooking, water heating, or any other than the heat pump.

BASES: Cooling 110° outside
80° inside

Heating 34° outside
72° inside

HOUSE: 6" blown fiberglass in ceilings. Heat reflecting foil back sheet rock insulation, furred out, leaving 1" dead air space on exterior walls.

Copper weather-stripping on all outside doors.

	MODEL 202, 202S 402 & 404 - 2½ HP	MODEL 401 - 2HP	MODEL 203U - 3½ HP
Heating Season Operating Cost	$ 79.00	$ 45.00	$105.00
Cooling Season Operating Cost	109.00	67.00	149.00
Total Annual Operating Cost Estimate	$188.00	$112.00	$254.00

These figures are based on normal operating conditions and should only be considered as approximations.

RW:ac
11/5/62